



The ground improvement specialist



Harbour stockyard project,
Cilegon, Indonesia

CMC

- + Dynamic Compaction
- + Controlled Modulus Columns
- + Prefabricated Vertical Drains
- + Menard Vacuum™ Consolidation
- + Vibro Stone Columns
- + Jet Grouting
- + Deep Soil Mixing
- + Dynamic Replacement
- + Vibrocompaction
- + Rapid Impact Compaction



Proceedings

20th SOUTHEAST ASIAN GEOTECHNICAL CONFERENCE
3rd AGSSEA CONFERENCE
In conjunction with
22nd HATTI ANNUAL SCIENTIFIC MEETING



www.menard-asia.com
www.menard-group.com

ISBN 978-602-17221-6-9



20th SOUTHEAST ASIAN GEOTECHNICAL CONFERENCE
3rd AGSSEA CONFERENCE

In conjunction with
22nd HATTI ANNUAL SCIENTIFIC MEETING

“Geotechnical Challenge for Mega Infrastructures”

Proceedings

Organized by :



AGSSEA
ASSOCIATION OF GEOTECHNICAL
SOCIETIES IN SOUTHEAST ASIA



Pullman Hotel - Jakarta, 6 - 7 November 2018

Supported by :



PT. Promisco Sinergi Indonesia (PT. PSI) adalah perusahaan yang bergerak di bidang konsultasi geoteknik dan geoteknik kegempaan, penyelidikan tanah, monitoring, kursus-kursus yang berhubungan dengan bidang geoteknik, dan pelatihan-pelatihan software geoteknik. PT. PSI didirikan oleh para tenaga ahli yang telah berpengalaman di bidang geoteknik lebih dari 16 tahun dan umumnya telah disertifikasi sebagai ahli geoteknik profesional utama (G-2) dan madya (G-1).

Visi Perusahaan

Mengjadi perusahaan konsultan di bidang geoteknik yang terbaik di Indonesia dan berstandar internasional

Misi Perusahaan

Membangun perusahaan yang dapat menyejahterakan pada tenaga ahli dan karyawan dengan berlandaskan pada hal-hal berikut :

- Standar etika profesional dan bisnis yang baik
- Meningkatkan kompetensi tenaga ahli dalam bidang geoteknik
- Senantiasa berusaha meningkatkan kualitas perusahaan

Pengalaman Perusahaan

- ◆ Pekerjaan Survey Topografi, Bathimetri dan Hidro Oceanografi Serta Investigasi Geoteknik Pembangunan Terminal Kijing, Mempawah (2018)
- ◆ Pekerjaan Penyedia Jasa Pekerjaan Jasa Konsultan Detailed Engineering Design (DED) Pembangunan Terminal Kijing, Mempawah
- ◆ Penyelidikan Tanah Grand Sawangan Depok (2018)
- ◆ Construction Supervision of The Boring Survey of Sulawesi Island Country of Indonesia (2018)
- ◆ Soil Investigasi dan Review Desain Perbaikan tanah East Cross Soekarno-Hatta International Airport Cengkareng (2018)
- ◆ Proyek Job 245 CTR-001 Feed For Badik and West Badik Field Development (2018)
- ◆ Proyek Pekerjaan Survey Soil Investigasi I, II & III Pematangan Lahan dan Kontruksi Apron Barat Ngurah Rai Denpasar Bali (2018)
- ◆ Proyek Tender Pematangan Lahan Pantai Sisi Barat Dan Konstruksi Apron Barat Bandara Udara International I Gusti Ngurah Rai, Denpasar, Bali (2018)
- ◆ Technical Advisor Lombok GECC Power Plant (Peaker) 130-155 MW (2017)
- ◆ Review Design Pada Proyek Pembangunan Jalan Tol Depok-Antasari (2017)
- ◆ D.LL



2018

ADVANCED & INNOVATIVE GEOTECHNICAL CONTRACTOR



"We're a professional entity specializing in geotechnical investigation, design, research, construction and consultancy"

BUSINESS OVERVIEW

PT. Geotekindo is a professional entity specializing in geotechnical investigation, design, research, construction and consultancy. Our parent company, Geoharbour Group (www.geoharbour.com), is a chief editor of China Standard of Reclamation Soil Treatment and a director member of Technical Committee of China Soft Soil Treatment. So far we have developed into a complex entity with business of dredging, road and bridge construction, foundation engineering and jetty construction.

300
LARGE-SCALE
PROJECTS
OVER PAST 10 YEARS

over
10,000Ha
soil treatment
involving a variety of job sites

over
1200Ha
ground improvement
in Indonesia

patented our technology beyond
30 cases
which is classified as
green technology

Some of Our Works

Singapore



VACUUM PRELOADING & PVD INSTALLATION WORKS
CHANGI INTERNATIONAL AIRPORT
Location: Terminal 5 Changi International Airport, Singapore
Method: Vacuum Preloading

Dubai, UEA



THE WORLD ISLANDS (THE HEART OF EUROPE)
Location: Dubai, UEA
Method: Vibro-compaction, Sheet Piling

Indonesia



PALEMBANG INDRALAYA TOLL ROAD
Location: South Sumatra, Indonesia
Method: Vacuum Preloading

Vietnam



FORMOSA HA TINH STEEL MILL
Location : Ky Anh Ha Tinh, Vietnam
Method : Various Method

Shanghai, China



PUDONG INTERNATIONAL AIRPORT
Location : Shanghai, China
Method : HVDM

Indonesia



GOLF ISLAND
Location : North Jakarta, Indonesia
Method : Dynamic Compaction and Vibroflotation

“Geotechnical Challenge for Mega Infrastructures”

Editor : *Masyhur Irsyam*
Ikuo Towhata
Ramli Nazir
Benson Hsiung
Paulus P. Rahardjo
Pintor Tua Simatupang
Didiek Djarwadi
Hendra Jitno
Widjojo A. Prakoso
Agus Setyo Muntohar
Nurly Gofar
Farid Ma'ruf
Endra Susila
Teuku Faisal Fathani
Gouw Tjie Liong
Erza Rismantojo

HIMPUNAN AHLI TEKNIK TANAH INDONESIA
INDONESIAN SOCIETY FOR GEOTECHNICAL ENGINEERING (ISGE)
Basement Aldeveco Octagon, Jl. Warung Jati Barat Raya No. 75
Jakarta 12740 - INDONESIA

PREFACE

Assalamu'alaikum Wr. Wb.

The Association of Geotechnical Societies in Southeast Asia (AGSSEA) consists of the Southeast Asian Geotechnical Society (SEAGS), Vietnamese Society for Soil Mechanics and Geotechnical Engineering (VSSMGE), Hong Kong Geotechnical Society (HKGES), Geotechnical Society of Singapore (GeoSS), Thai Geotechnical Society (TGS), Chinese Taipei Geotechnical Society (CTGS), Indonesian Society for Geotechnical Engineering (HATTI) and Malaysian Geotechnical Society (MGS). It was decided at the General Committee meeting of SEAGS and AGSSEA on 31 May 2016 at Kuala Lumpur that the 20th Southeast Asian Geotechnical Conference and the 3rd AGSSEA Conference (20SEAGC-3AGSSEA Conference) is to be held at Pullman Hotel in Jakarta, from 6-7 November 2018. This is the first time in history of SEAGS that the conference is held at Jakarta, Indonesia, therefore the conference is also in conjunction with 22nd Annual Indonesian National Conference on Geotechnical Engineering.

The theme of 20SEAGC-3AGSSEA Conference is "Geotechnical Challenge for Mega Infrastructure", to indicate how mega infrastructure rapidly constructed by Indonesian Government. This conference will cover the wide range topics:

1. Foundation and its problem
2. Deep excavation, basement and tunnels
3. Unsaturated soil mechanics,
4. Sedimentary and residual soils
5. Soft soils and marine foundation
6. Geotechnical and earthquake engineering
7. Geotechnical instrumentation
8. Ground subsidence and sea-water intrusion
9. Vibration and earthquake effect to the structure
10. Soil improvement
11. Slope stability
12. Geo-environmental engineering
13. Finite element method

There will be special keynote address delivered by Ministry of Public Work and Housing of Indonesia, 11 keynote lectures and 84 technical papers to be presented in parallel sessions.

Deep condolences for all victims during the Lombok - Palu - Donggala earthquakes. Liquefaction, flows and deep slide shown as phenomenon during the disaster.

Special gratitude to Menard as main sponsored, Geotekindo and Bauer as co-sponsored and all sponsored who participate in this conference.

Wassalamu'alaikum Wr. Wb.
Jakarta, 6 November 2018

Dr. Pintor T. Simatupang
Conference Chairman

MESSAGE FROM PRESIDENT OF INDONESIAN SOCIETY FOR GEOTECHNICAL ENGINEERING (ISGE)

Dear our honorable guest,

Dr. Basoeki Hadimuljono-Minister of Public Works and Public Housing of the Republic of Indonesia, Prof. Charles Ng - President of the International Society for Soil Mechanics and Geotechnical Engineering (ISSMGE), honorable guests from South East Asian Geotechnical Society (SEAGS) and Association of Geotechnical Societies in South East Asia (AGSSEA), board members of the Indonesian Society for Geotechnical Engineering (ISGE), Chairman of the Engineering Commission of the Indonesian Academy of Sciences, and all Participants; Welcome to our International Conference. This year we held the 20th SEAGSC together with 3rd AGSSEAC in conjunction with our 22nd ISGE annual conference.

“Geotechnical Challenge for Mega Infrastructure” become our theme to answer the challenge we face together from current rapid infrastructure construction. Many geotechnical construction was built in accordance with good soil mechanics and geotechnical understanding, but we need more than that. We need all stages in construction industry can work together, from theory, practical construction, detailing works, comprehensive supervision, and of course the quality assurance process. We need all parties to collaborate together, to move fast forward without no chance for mistake nor failure. No time for failure, ISGE/HATTI collaborate with all parties (national and international) try to ensure there is only one way, and its forward moving.

We understand that there is still many holes in our construction process, not only cause by man made construction but also by the mother of nature. We saw how horrible the Donggala – Palu earthquake last month and we mourn for the caused; but as engineer, we stand; we seek the cause, we learn, we give suggestion and the more important, we stand still, not only as engineers but also as a nation. We stand for the humanity-our pray for them.

Allow us to convey our gratitude to Menard, our main sponsored, Geotekindo and Bauer as our co-sponsored and all sponsored who participate in this event. Also to all speakers, writers, participants, especially to all committee who works to their best for the success of this event.

Last but not least, hopefully this event will bring good and new point of view seeing the geotechnical engineering. Please enjoy the event.

Geotechnical in our heart!!!

Jakarta, 6 November 2018
Indonesian Society for Geotechnical Engineering

Prof. Ir. Masyhur Irsyam, MSCE., Ph.D.
President

ORGANIZING COMMITTEE

- Advisor : Prof. Ir. Masyhur Irsyam, MSE, Ph.D
- Conference Chairman : Ir. Pintor Tua Simatupang, MT. Dr-Eng
- Conference Co-chair : Prof. Ir. Paulus P. Rahardjo, MSCE, Ph.D
- Secretary : Aksan Kawanda, ST. MT.
- Treasurer : Ir. Idrus M. Alatas, MSc. Ph.D
- Technical Papers : Prof. Ir. Masyhur Irsyam, MSE, Ph.D
Prof. Ikuo Towhata
Dr. Noppadol Phienwej
Prof. Chu Jian
Prof. Eun Chul Shin, Ph.D
Prof. Harianto Rahardjo
Prof. Dr. Ir. Ramli Nazir
Ir. Pintor Tua Simatupang, MT. Dr-Eng
Prof. Ir. Paulus P. Rahardjo, MSCE, Ph.D
Prof. Ir. Widjojo A. Prakoso, MSCE, Ph.D
Prof. Agus Setyo Muntohar, ST. M.Eng.Sc, Ph.D
Ir. Nurly Gofar, MSCE, Ph.D
Dr. Ir. Didiek Djarwadi, MSc
Ir. Hendra Jitno, MAsC, Ph.D
Ir. Endra Susila, MT., Ph.D.
Dr. Ir. Gouw Tjie Liong, M. Eng
Ir. M. Farid Ma'ruf, MT. Ph.D
- Event : Ir. Fauzi Buldan Y.
Ir. Wawan Kuswanda, MT.
Ir. Dandung S. Harninto, MT
Ali Iskandar, ST. MT.
Yunan Halim, ST. MT.
Dayu Apoji, ST. MT
Reza Ismaniar, ST. MT.
Andri Mulia, ST. MT.
Edwin L., ST. MT.
Laksamana M. Sakti, ST. MT
Merry Natalia, ST. MT.
Amelia Yuwono, ST. M.Kom

- Sponsorship : Anthony Setiawan, MBA
Marcello Djunaidy, ST. MT.
- Secretariat : Josephine Aristiti Setyarini, ST. MT.
Aflizal Arafianto, ST.
Sugino
- Publisher : Himpunan Ahli Teknik Tanah Indonesia
(*Indonesian Society for Geotechnical Engineering*)
- Address : Basement Aldevco Octagon
Jl. Warung Jati Barat Raya No. 75
Jakarta 12740
Telp. : 021 - 7981966
Fax. : 021 - 7974795
Email : sekretariat@hatti.or.id; hattipusat@yahoo.com
Website : <http://www.hatti.or.id>
- ISBN No. : 978-602-17221-6-9

TABLE OF CONTENTS

Preface Committee Chairman	i
Message from President of Indonesian Society for Geotechnical Engineering (ISGE)	ii
Organizing Committee	iii
Table of Contents	v

Keynote Speakers :

1. Wastes Cover Wastes: A Novel, Scientific and Environmentally Friendly Approach for Landfilling (<i>C.W.W. Ng¹, J.L. Coo¹, H.W. Guo¹ and B.W. Lu¹ - ¹Department of Civil and Environmental Engineering, Hong Kong University of Science and Technology, HKSAR</i>)	1-4
2. Damages Associated with Geotechnical Problems in 2018 Palu Earthquake, Indonesia (<i>Masyhur Irsyam^{1,2,3,9}, Nuraini Rahma Hanifa^{1,3}, Andhika Sahadewa^{1,2}, Agus Setyo Muntohar^{2,4}, Widjojo Adi Prakoso^{2,5}, Dandung Sri Harninto², Didiek Djarwadi^{2,3}, M. Ridwan³, Danny Hilman Natawidjaja^{3,6}, Mudrikk Daryono^{3,6}, Endra Gunawan^{1,3}, Irwan Meilano^{1,3}, Astyka Pamumpuni^{1,3}, Ariska Rudyanto^{3,7}, Sigit Pramono^{3,7}, Ramli Nazir⁸ Institut Teknologi Bandung (ITB)²Indonesia Society for Geotechnical Engineering (HATTI)³National Center for Earthquake Studies (PuSGeN), Ministry of Public Work and Housing⁴Universitas Muhammadiyah Yogyakarta (UMY)⁵Universitas Indonesia (UI)⁶Indonesian Institute of Sciences (LIPI)⁷Indonesian Agency for Meteorology, Climatology and Geophysics (BMKG)⁸Universiti Teknologi Malaysia (UTM)⁹Indonesian Academy of Sciences (AIPI)</i>).....	5-14
3. Piling Construction and Testing of Megastructures on Problematical Soil Ground of Kazakhstan (<i>A.Zhussupbekov¹ and A.Omarov¹ Department of Civil Engineering, L.N. Gumilyov Eurasian National University, Astana, Kazakhstan (Prof. Askar Zhussupbekov)</i>).....	15-18
4. Serious Lessons Learnt from Big Project (Ikua Towhata, <i>Professor Emeritus, University of Tokyo, Visiting Professor, Kanto Gakuin University</i>)	19-24
5. Stability Analysis of Buried Waste Water Pipeline in Soft Ground (<i>Prof. Eun Chul Shin-Korea University - South Korea</i>).....	25-28
6. New Solutions to Geotechnical Challenges for Coastal Cities (<i>J. Chu¹, S.F. Wu¹, H. Chen¹, X.H. Pan¹, and K. S-L. Chaim² ¹School of Civil and Environmental Engineering, Nanyang Technological University, Singapore, ²Geological and Underground Projects Department, Build Control Authority, Singapore</i>)	29-34
7. Use of Strut Free Systems in Deep Excavations (<i>Chang-Yu Ou¹ and Aswin Lim² ¹National Taiwan University of Science and Technology, Taipei, Taiwan, ROC ²Department of Civil Engineering, Universitas Katolik Parahyangan, Bandung 40141, Indonesia</i>)	35-38

8.	Behavior of Single Pile and Pile Group Foundation for High Rise Buildings on Expansive Soils (Prof. Paulus P. Rahardjo-Universitas Katolik Parahyangan, Indonesia).....	39-45
9.	Challenges in Design and Construction of Deep Excavation and Case Histories (Dato' Dr. Ir. Gue See Sew. CEO of G & P Professionals, Malaysia).....	46-54
10.	Increasing geotechnical challenges in the design and construction planning of the Third Phase Bangkok MRT Underground (N. Phienwej ¹ , A. Asanprakit ² , P. Kittiyodom ² and S.Timpong ² ¹ School of Engineering and Technology, Asian Institution of Technology, Pathumthani, Thailand ² Geotechnical and Foundation Engineering Co. Ltd., Bangkok, Thailand).....	55-60
11.	Mega Reclamation Projects: Challenges and Lessons Learned in Soil Improvement Works and Acceptance Tests (K. Yee ¹ and S. Varaksin ² ¹ Association of Geotechnical Societies in South East Asia (AGSSEA), Kuala Lumpur, Malaysia ² Apageo, Paris, France).....	61-74

Session I.A1 – Pile. (TC 212)

1.	Design and Construction of Foundation System for Malaysia First Drawbridge at Kuala Terengganu (Shaw-Shong Liew, Kuan-Seng Koo and Fong-Wah Chee).....	75-80
2.	Advancement of Bearing Capacity and Settlement Analyses of Piled-Raft Foundation (Sugeng Krisnanto, Iwayan Sengara and Fithrie Nur Adelina)	81-84
3.	Effect of Intermediary Weak Layer on The Behaviour of Piled Raft (Venkatraman Balakumar, Huang Min, Erwin Oh and Arumugam Balasubramaniam).....	85-91
4.	Analysis of In Situ Laterally Loaded Tests on Caisson Foundations (Jiunn-Shyang Chiou and Cheng-Chang Tsai).....	92-95
5.	Study of Bored Pile Capacity in Klang Valley Residual Soil Based on Field-Performance Data (Allan Chwee Yew Lun, Balakrishnan Etty Gaunder and Nazri Ali).....	96-101
6.	Foundation Value Engineering & Underpinning Using Micropile for Building Upgrading Works (Kai Ming Lee and Elly Norissya Mohd Said).....	102-106
7.	Interpretation on Performance of Two Drilled Shafts Subjected to Tensile Loading Considering Concrete Cracking Effect (San-Shyan Lin, Tai-Hong Chen and Chia-Hong Lai).....	107-110
8.	Pile Settlement Uncertainty in Jakarta, Indonesia (Bondan Satria and Widjojo Adi Prakoso).....	111-114

9. Re-Evaluation of Pile Capacity due to Shallow Gas – A Malaysia Case Study (*Christian Hariady Girsang, Noorizal Nasri Huang, M Syazwan Kamil Abdullah, M Razi Mansoor, Muhammad Joehan Rohani, Azam A Rahman and Wan M Marzuki Wan Ismail*)..... 115-120

Session II.A2 - Pile & Instrumentation. (TC 212)

10. Application of Newly Developed Real- Time Website-base GIS Monitoring in Tunnelling (*Christian Luis, Johnny Huang and Bin-Chen Benson Hsiung*)..... 121-124
11. ERT-Based Leakage Tracing for Dam Safety and its Potential Sliding Surface (*Helsin Wang, Chih-Hsin Hu, Sheng-Hsiung Hsieh and Yao-Chu Tsai*)..... 125-135
12. Dynamic p-y Curves for a Single Pile by 1g Shaking Table Tests (*Sangseom Jeong*).. 136-140
13. Design Method for Bottom Single Blade Steel Rotation Pile Foundation : Case study in Vietnam (*Duy Lam Dao and Thi Tuyet Trinh Nguyen*)..... 141-146
14. Active Shaking Tests of Pile Foundation Models in Dry Sand Ground (*Kohei Kenda, Anh Tuan Vu and Tatsunori Matsumoto*)..... 147-157
15. Estimating Pile Axial Bearing Capacity by c-phi' Derived from Pressuremeter Test (*Tjie Liong Gouw*)..... 158-167
16. Volume Measurement for Heavy Punding Induced Craters and Ground Heave (*Amalia Ula Hazhiyah, Hung-Jiun Liao and Chih-Jung Chien*) 168-178
17. Potentiality of Boehmeria Nivea as Alternative Material in the Production of Geotextile (*Oliver Celis, Catalino Mendoza, Ernesto Villarica, Ederick Songahid and Ann Krischel Hipolito*) 179-183
18. A Multidisciplinary Ground Model Approach to Geotechnical and Geohazard Site Appraisal for Large Infrastructure Developments (*D. Rushton*) 184-187
19. Prediction of the Geological Condition for Pipe jacking Base on the Data Collected in the Shafts (*Jian Shou Keh and Kan Tang Fu*) 188-192

Session III.B1- FEM. (TC 103)

20. A Case Study On Monitoring and Numerical Analysis of Groundwater Variation and Inclinator Displacement in Taiwan (*Ching-Jiang Jeng and Chia-Yu Yang*) 193-197

21.	Numerical Simulations of an Excavation Case in Jakarta by Hypoplasticity Model for Clays (<i>Melisa Kosasi, Fuchen Teng and Benson Hsiung</i>)	198-203
22.	3D Finite Element Analysis of Deep Excavation in Central Jakarta using Total and Effective Shear Strength Properties. (<i>Tatag Yufitra Rus, Bin-Chen Benson Hsiung and Kuo-Hsin Yang</i>)	204-212
23.	Plane Strain Ratio and Waling Size Evaluation of Deep Excavation in Kuala Lumpur Using 3D Finite Element Analysis (<i>Jen Shen Ang, Bin Chen Hsiung and Ching Hung</i>).....	213-221
24.	Assessment of Mechanical Behavior of Granular Soils Adopting Various Plasticity Models (<i>Deepa Patil, Anitha Kumari S D and Nimmy Mariam Abraham</i>).....	222-227
25.	Remediation of Oil Tank Using PLAXIS 3D (<i>Anthony Gunawan</i>).....	228-233
26.	Dynamic Analysis of Underwater Tunnels (<i>Akhila Babu, Anitha S D and Nimmy Mariam Abraham</i>).....	234-237
27.	3D Finite-Element Analysis on Behaviours of Pile Group and Piled Raft Foundation Models Subjected to Cyclic Horizontal Loading (<i>Anh-Tuan Vu and Tatsunori Matsumoto</i>).....	238-244
28.	Finite Difference Analysis of Raft Foundations under Vertically Static Loads (<i>Der-Wen Chang and Hsin-Wei Lien</i>).....	245-250

Session IV.B2 - Soil Mechanics & Lab. (TC 101 & TC 102)

29.	Determining Unsaturated Soil Properties Through Parameter Estimation (<i>Ibrahim Ibrahim, Didit Nur Arif and Nurly Gofar</i>).....	251-255
30.	Stochastic Estimation of Consolidation Settlement of The Upper Pleistocene Clay Layer in Osaka Bay Using a Particle Filter Method (<i>Shotaro Kubota1 and Kazuhiro Oda2</i>)	256-257
31.	Volcanic Cohesive Soil Behavior under Static and Cyclic Loading (<i>Wa Ode Sumartini, Hemanta Hazarika, Takaji Kokusho and Shinichiro Ishibashi</i>).....	258-264
32.	Screw Driving Sounding Test for Soil Identification and Classification (<i>Aminaton Marto, Go Sakai, Naoaki Suemasa, Nor Zurairahetty Mohd Yunus, Siti Norafida Jusoh, Nadiah Jamaludin, Muhammad Mustakim Ponimin and Muhammad Fakrulnizam Mohd Tahir</i>).....	265-270
33.	Argillaceous Rock Properties Changes Due to the Weathering Process (<i>Idrus M. Alatas, Masyhur Irsyam, Ramli Nazir and Pintor T. Simatupang</i>)	271-277

34.	Investigation of Aqueous Phase Liquids Migration in Double-Porosity Soil under Isothermal and Non-Isothermal Effect (<i>Loke Kok Foong, Prof. Ir. Dr. Ramli Nazir and Assistant Professor Dr. Hossein Moayedi</i>)	278-283
35.	Lessons Learned from Pressuremeter Tests on Stone Columns (<i>Richard Ong</i>).	284-287
36.	Correlations Between Gradation, Physical and Mechanical Parameters for Material Embankments Reclamation (<i>Herman Wahyudi and Yudhi Lastiasih</i>)	288-291
37.	Characterization of Leachate Distributions at Ngipik Municipal Solid Waste Disposal site in East Java - Indonesia (<i>Ria Asih Aryani Soemitro, Dwa Desa Warnana and Nila Sutra</i>)	292-296

Session V.C1- Earthquake. (TC 203)

38.	Evaluation of Remedial Works for a Spillway on Landslide-dammed Lakes by an Earthquake, a Case Study in the Jiufengershan Landslide (<i>Ihui Chen, Sheichen Ho, Yushu Lin, Junyang Chen and Miaubin Su</i>)	297-300
39.	A Comparison Between VS30 Based- and Natural Frequency Based-Site Amplification Factor for Three Different Types of Soil Classification (<i>Bonifacius Yogatama and Budiwan Adi Tirta</i>)	301-306
40.	Maps of Corner Period (T _c) of Response Spectra In City of Jakarta (<i>Delfebriyadi Delfebriyadi</i>).....	307-309
41.	Analysis of Bedrock Synthetic Ground Motion on Bandung City using PSHA Method (<i>Arifan Jaya Syahbana, Anggun Mayang Sari and Eko Soebowo</i>)	310-315
42.	Influence of Cyclic Behaviour of Vibratory Pile Driving And Surging on Pile Performance Observed in Model load Tests in Dry and Saturated Sand Grounds (<i>Shunsuke Moriyasu, Mako Aizawa, Tatsunori Matsumoto, Shun-Ichi Kobayashi and Shinya Shimono</i>).....	316-322
43.	Dynamic Compaction at New Yogyakarta International Airport for Liquefaction Mitigation (<i>Ryan Rahmat Setiaji, Abi Maulana Hakim, Febrini Hartianty Adinda and K.M. Abuhuroyroh</i>).....	323-328
44.	Field Identification of Active Fault Nearby the Footprint of the Dam (<i>Didiek Djarwadi, D.H. Natawidjaja and M.R. Daryono</i>).....	329-333
45.	Seismic Analysis of El-Agrem Concrete Face Rockfill Dam (<i>Merouane Abdellaoui and Belkacem Moussai</i>).....	334-336
46.	Effects of Vibrating Frequency of a Plate Compactor on Soil Density (<i>Yung-Show Fang</i>).....	337-340

Session VI.C2 - Slope Stability. (TC 208)

47.	Using Time Domain Reflectometry for Monitoring Slope Movement in the Jiufenershan Landslide (<i>Sheichen Ho, Ihui Chen, Yushu Lin, Junyang Chen and Miaubin Su</i>)	341-345
48.	Application of Data Mining Technique to Complement Photogrammetric Roughness Data (<i>Dong-Hyun Kim, Arumugam Balasubramaniam, Ivan Gratchev and Chul-Ho Lee</i>)	346-349
49.	Case Studies of a Partially Collapsed RS Wall at a Building Site (<i>Balakrishnan ETTY Gaunder, Allan Chwee Yew Lun and Mohd Redzuan Ahmad</i>)	350-356
50.	Numerical Simulation of Some Debris Flow Events in Central Java for Predicting Run-out Distributions (<i>Imam Achmad Sadisun, Rendy Dwi Kartiko and Indra Andra Dinata</i>)	357-360
51.	Channeled landslide Protection Using Flexible Barriers (<i>Thomas Hangartner, Prosida Rhapsody and Christophe Balg</i>)	361-367
52.	Research on Failure of Aeolian Sand Roadbed Slope Through Laboratory Static Load Test (<i>Xiukun Dong and Liying Liu</i>)	348-371
53.	Stability Analysis of an Overall Failure Excavation Case in Hang Zhou (<i>Tuan Nghia Do</i>)	372-374
54.	Effect of the Initial Suction Boundary on the Slope Failure of Volcanic Residual Soil (<i>Agus Setyo Muntohar</i>)	375-378

Session VII.D1 - Soil Improvement. (TC 211)

55.	Applying In Situ Debris-cement Mixtures to the Ground Improvement of Bank in Wild Creeks (<i>Junyang Chen, Ihui Chen, Yushu Lin, Sheichen Ho and Miaubin Su</i>)..	379-382
56.	Dynamic Compaction of Lateritic Fill for Property Development (<i>Richard Ong and Marini Mardi</i>).....	383-387
57.	Settlement Ratio Determination of Vacuum Preloading Soil Improvement Technique (Case Study at Palindra Toll Project Section 1) (<i>Herwan Dermawan, Masyhur Irsyam, Bigman M Hutapea, Endra Susila, Rizal Sutjipto and Idwan Suhendra</i>).....	388-391
58.	The Settlement Evaluation of Improved Soft Clay Using LECA Replacement Technique (<i>Azhani Zukri, Ramli Nazir and Ng Kok Shien</i>)	392-397
59.	Performance of Helix Piled Raft in Tropical Fibrous Peat Soil under Traffic Loads (<i>Ardy Arsyad, Ahmad Bakri Muhiddin and Lawalenna Samang</i>)	398-401

60.	Effect of Compaction on Liquefaction of River Sand and Sea Sand in Hai Phong City, Vietnam (<i>Chau Lan Nguyen, Quang Phuc Nguyen, Hai Ha Nguyen and Duc Manh Nguyen</i>)	402-408
61.	Proposal of Permeability Evaluation Method of Suspension Grout (<i>Kentaro Uemura, Takamitsu Sasaki, Naoaki Suemasa, Kazuya Itoh, Koichi Nagao and Shunsuke Shimada</i>)	409-414
62.	Compacted Polymer-Enhanced Bentonite-Sand Mixture – Behaviour and Potential Applications (<i>Agus Setianto Samingan and Yulian Firmana Arifin</i>)	415-420
63.	Geosynthetic Reinforced Road Structure as Fast Rehabilitation for a Typhoon Disaster (<i>Hermina Ho, Jeff Yang and Henry Sie</i>)	421-424

Session VIII.D2 – Soft Soil. (TC 204)

64.	The use of the Observational Method in the Deep Excavations for the Realization of a Residential Compound (<i>Marco Carassini, Filippo Bucci and Andrea Antiga</i>)	425-432
65.	Reliability Assessment on Deep Braced Excavations Adjacent to High Slopes in Mountain Cities (<i>Runhong Zhang, Wengang Zhang, Zhongjie Hou and Wei Wang</i>)	433-438
66.	Numerical Investigation of Wall Deflections Induced by Braced Excavations in Sands (<i>Hou Zhongjie, Zhang Wengang, Zhang Runhong and Wang Wei</i>)	439-444
67.	Singapore Downtown Line 3 - Tunnelling Challenges in Soft Soil and Under Conserved Structures (<i>Michael McGowan, Sofren Leo Suhaendi and Gordon Lee</i>).	445-450
68.	Seasonal Variation of Water Content and Pore-water Pressure Distribution in Vegetated Soil Slope (<i>Nurly Gofar, Harianto Rahardjo and Alfrendo Satyanaga</i>)	451-456
69.	Strength Characteristics of Cement-treated Peat in Sumatera Island, Indonesia (<i>Hirochika Hayashi, Takahiro Yamanashi, Hijiri Hashimoto, Eddie Suraryo, Fahmi Aldiamar, Maulana Iqbal and Dea Pertiwi</i>)	457-460
70.	Basement Excavation in Soft Marine Clay in Bukit Tinggi, Klang (<i>Sharmeelee S.</i>)	461-464
71.	Effect of Rapid Impact Compaction Energy on Unconfined Compressive Strength Properties of Fill Clay Soil (<i>Arifin Beddu, Lawalenna Samang, Tri Harianto and Achmad Bakri Muhiddin</i>)	465-468
72.	A Study on Soft Soil Stabilization by Mass Stabilization Methods for Construction of Dike and Rural Roads (<i>Vinh An Phung, Van Tuan Le and The Quynh Do</i>)	469-464

Session IX.E1 – Deep Excavation & Tunnel. (TC 204)

73.	Study for Structural Performance of Steel Sheet Piles Used for Retaining Wall (<i>Eka Susanto, Matsui Nobuyuki and Otsushi Kazutaka</i>)	475-481
74.	Protection of the Existing Railway Tunnels from an Adjacent Deep Excavation (<i>Jung-Feng Chang, I-Chou Hu, Chun-Seng Hsu and Huei-Ting Chang</i>)	482-486
75.	Bored Pile Retaining Wall Solutions for Earthquake Slip 6 AT Ohau Point, Kaikoura, New Zealand (<i>Senthuran Arulanantham, Anthony Fairclough, Sam Glue and Jody Edwards</i>)	487-493
76.	Effects of Cross Wall to the System Stiffness of Deep Excavations in Clay (<i>Zih-Yun Wang, Bin-Chen Benson Hsiung, Hsii-Sheng Hsieh and Louis Ge</i>)	494-499
77.	Ground Surface Settlement Induced by Diaphragm and Buttress Walls Installation: Numerical Study (<i>Aswin Lim and Pio Go Hsieh</i>)	500-503
78.	Evaluation of Surface Settlement and Lateral Displacement During Tunnel Construction Using 3D Numerical Modelling (<i>Fahmi Aldiamar, Desyanti Desyanti, Masyhur Irsyam, Bigman M. Hutapea, Endra Susila, Riska Muslimah and Weni Maulina</i>)	504-508

Session X.RE2 - Other Sessions & Indonesian Class

79.	Aplikasi Metode Elemen Hingga dan Kriteria Runtuh Papaliangas Batuan Berkekar : Problem-Problem Analisa Terowongan, Kestabilan Lereng dan Wellbore Stability dalam Mekanika Batuan (<i>Wilham George Louhenapessy</i>)	509-514
80.	The Application of Active Lime & Cement as Soil Stabilization Material (<i>Renggo Ginanjar, Wilham G. Louhenapessy, Asrul Ahdar</i>)	515-518
81.	Perbandingan Analisa Perkuatan Lereng dengan Jangkar : Program dan Manual (<i>Wawan Kuswaya and Wilham G. Louhenapessy</i>)	519-522
82.	On the Weak Limestone Rock Slope Stability Analysis (<i>Wilham George Louhenapessy</i>)	523-530
83.	Slope Stability Anayses using Probabilistic Approach (A Case study in Grobogan, Central Java) (<i>Febryansyah Dwi Riyadinata, Yusep Muslih Purwana, Niken Silmi Surjandari and Noegroho Djarwanti</i>)	531-534
84.	Perancangan Proteksi Galian Dalam Dengan <i>Soldier Pile</i> . Studi Kasus : <i>Underpass</i> Pada Pusat Perbelanjaan di Kawasan Jakarta Selatan (<i>Siska Rustiani and Ryan Alexander Lyman</i>)	535-538

85.	Study of Slope Failure and Reinforcement Analysis to Restore and Increase the Slope Stability in Flores, East Nusa Tenggara Using Plaxis 2D and 3D <i>(Rendra Priatno¹, Ali Iskandar², and Jo Lian Huat³)</i>	539-543
86.	Study on The Effects of Vibration due to Pile Driving by Empirical Formulas and Continuous Monitoring <i>(Stefanus Diaz Alvi¹, Ricky Setiawan², Andy Sugianto³, Paulus P. Rahardjo⁴)</i>	544-548
87.	Pengaruh Tahanan Ujung Tiang dan Faktor Aman Terhadap Lendutan Pelat Terpakai Tiang Tunggal Pada Lempung Lunak <i>(P. Anas¹, O. Ferly², M. Roza³)</i>	549-543
88.	Application of Distributed Fibre Optic Sensor (DFOS) in Bi-directional Static Pile Load Tests <i>(Lee Siew Cheng¹, Tee Bun Pin¹, Chong Mun Fai¹, Hisham Mohamad² and Ang Koh An³, Paulus P. Rahardjo⁴)</i>	554-560
89.	Design of Simple Drapery Systems for Rock Cuts and Natural Slopes <i>(Matteo Lelli¹, Alberto Grimod², Riccardo Laneri¹, Deny¹, Vincent Setiawan², Dinda Mutiara Savitri¹)</i>	561-568
90.	Emergency Works and Landslide Remediation using Geosynthetics Reinforced Soil Structures – Recent Indonesian Case Studies <i>(Deny¹, Matteo Lelli², Dinda Mutiara Savitri³)</i>	569-573
91.	Geotechnical Properties of Cement-Stabilized Mine Tailings from Brgy. Gango, Libona, Bukidnon, Philippines <i>(Einstine M. Opiso, Reinerio P. Supremo, Reymar T. Rejas and Jemima R. Perodes)</i>	574-581
92.	A New Breakthrough – Application of Control Modulus Column for Settlement and Stability Control under Soft Soil and High Embankment Load at Pemalang-Batang Toll Road <i>(Ryan Rahmat Setiaji¹, Panji Utomo², KM. Abuhuroyroh³)</i>	582-591
93.	Estimasi Modulus Resilien dari uji CBR pada Tanah Lempung distabilisasi Abu Vulkanis dan Kapur <i>(Devi Oktaviana Latif - Dr.,ST.,M.Eng, Ahmad Rifa'i- Dr., Ir.,MT., Latif Budi Suparma –Ir.,M.Sc., Ph.D)</i>	592-596
94.	Seasonal Variation of Water Content and Pore-water Pressure Distribution in Vegetated Soil Slope <i>(N. Gofar¹, H. Rahardjo¹, A. Satyanaga¹ - ¹School of Civil and Environmental Engineering, Nanyang Technological University, 50 Nanyang Avenue, Singapore. 639798)</i>	597-602
95.	Efek EPS Geofom sebagai Material Pengisi terhadap Nilai CBR Laboratorium pada Tanah Kohesif Darah Bandung <i>(Lestari, A. S¹ and Julian Clementio² - ¹Dosen Universitas Katolik Parahyangan, Bandung, Indonesia, ² Mahasiswa Universitas Katolik Parahyangan, Bandung, Indonesia)</i>	603-606
96.	Prediction of Excess Pore Pressure Due to Pile Driving Based on CPTu <i>(A. Arafianto¹ and P.P. Rahardjo². ¹Engineering Faculty, Universitas Katolik Parahyangan Bandung, Indonesia ²Engineering Faculty, Universitas Katolik Parahyangan, Bandung, Indonesia)</i>	607-610

97. Increasing geotechnical challenges in the design and construction planning of the Third Phase Bangkok MRT Underground (*N. Phienwej¹, A. Asanprakit², P. Kittiyodom² and S.Timpong²* ¹*School of Engineering and Technology, Asian Institution of Technology, Pathumthani, Thailand* ²*Geotechnical and Foundation Engineering Co. Ltd., Bangkok, Thailand*)..... 611-616

Compacted Polymer-Enhanced Bentonite-Sand Mixture – Behaviour and Potential Applications

S.S. Agus¹ and Y.F. Arifin²

¹Engineering Consultancy Firm, Singapore

²Civil Engineering Department, Lambung Mangkurat University, Banjarmasin, Indonesia

E-mail: agus72indo@gmail.com

ABSTRACT: An investigation into behaviour and potential applications of a polymer-enhanced bentonite-sand mixture (PEBSM) in its compacted state had been carried out in an environmental controlled laboratory. The experiments undertaken included microscopic visualization of the mixture, drying-wetting processes, consolidation and shear strength tests. The results obtained indicate that depending on the overburden pressure acting on the compacted mixture and its water content, settlement in combination with swelling and shrinkage may result in cracks or on contrary may close the initial cracks induced by the mechanical compaction in the field. The conclusions have been drawn based on an analytical assessment performed on the field and laboratory data gathered. A discussion is also brought up on the difference between two approaches used – single-valued effective stress and two-independent stress state variable approaches. The two approaches predict different values of suction at which crack starts to occur and different time-settlement behaviour.

Keywords: Bentonite, swell/shrink, settlement, shear strength, unsaturated soils, cracks.

1. INTRODUCTION

Polymer-enhanced bentonite-sand mixture (PEBSM) has been adopted as landfill liner and/or landfill cover in several countries particularly in Europe. A study on a PEBSM was undertaken pertaining to this application and a field measurement was taken in a location in Germany. This innovative material was developed for the landfill usage and mainly consists of a granular material (sand) mixed with a small amount of sodium type bentonite and a minute amount of polymer with certain proportions. The following figures show the environmental scanning electron microscopy photos taken and reported by Agus et al. (2007). The photos clearly depict bentonite-polymer nets that have been formed when water is added to the mixture. The minute amount of polymer added to the mixture covers the surface of bentonite clusters and sand grains.




Figure 1 Polymer in interaction with bentonite particles (from Agus et al., 2007)

The bentonite presence is beneficial to the hydro-mechanical behaviour as reported earlier by Arifin et al. (2006). As described in various publications, the magnitude of swelling pressure of compacted samples containing bentonite and its hydraulic conductivity depend on the dry density of the compacted material.

Depending on the magnitude of vertical pressure acting in the field, the compacted mixture, when in contact with water, may exhibit swelling or settlement and/or cracks under the influence of weather i.e. during drying-wetting cycles. In contrast, another possible scenario may occur, whereby initial cracks earlier induced by mechanical compaction or some other processes close during the cycles.

During drying cycle, it is highly possible that suction exists in the compacted mixture and its magnitude changes with time and may reach zero value when saturation is attained. The addition of polymer in the mixture improves resistance of the compacted material to crack. Visual observation made by Schanz et al. (2004) indicates that when exposed to the same suction value the compacted PEBSM exhibits no apparent cracks in contrast to the compacted mixture without polymer addition.




Figure 2 Crack developed under suction application on compacted specimens (from Schanz et al., 2004)

Theoretically, the development of cracks in the compacted mixture can be predicted utilising the unsaturated soil principles. Two different approaches can be used for this purpose; namely, using the single-valued effective stress concept and the two-independent stress state variables approach. This is the subject brought out in this paper. Data from a field measurement have been utilised in the study. Critical suction at which cracks start to occur is also formulated.

2. FIELD TEST DATA

The field test data that have been used in the study had been gathered from a landfill site located in Germany. A test field of about 2,800 m² in area had been established at the site, where suction measurement by means of tensiometer had been undertaken in the PEBSM layer for about 4.5 years' duration.

The degree of saturation of the PEBSM was calculated from the measured suction (in this case matric suction) using its soil-water characteristic curve, which was measured and reported in Schanz et al. (2004).

The SWCC of the compacted PEBSM portrays its good water retention characteristic as indicated by a small drop in the degree of saturation over a "wide" range of suction (up to 100 kPa).




Figure 3 Measured matric suction and computed degree of saturation of the compacted PEBSM layer




Figure 4 Soil-water characteristic curve for the compacted PEBSM specimen (from Schanz et al., 2004)

On site, the PEBSM was laid approximately 1 meter deep from the final ground surface leading to a surcharge of approximately 20 kPa or slightly lesser. The initial conditions of the PEBSM in the field test are as following:

- Initial dry density (γ_d) : 1.75 Mg/m³
- Initial void ratio (e) : 0.52
- Initial water content (w) : 5%
- Initial degree of saturation (S_r) : 25.6%

With a 1-m thick recultivation and drainage layer, the total vertical overburden stress acting in the middle of the compacted PEBSM of 7 cm can be computed to be equal to 20.6 kPa.

3. STRESS-STRAIN RELATIONSHIP

As described in the preceding section, the field experimental data had been analysed based on two approaches; namely, the single-valued effective stress concept and the two-independent stress state variables approach. The formulation of both approaches is described below.

3.1 Single-Valued Effective Stress Concept

This concept is based on the framework proposed by Bishop (1959), which is formulated as:

$$\sigma = (\sigma - u_a) + \chi s \tag{1}$$

Where $(\sigma - u_a)$ is the net stress, χ is a coefficient which depends mainly on the degree of saturation, S_r , soil structure and cycle of wetting, drying, or stress change, and s is suction, which is defined as matric suction or $(u_a - u_w)$.

The χ coefficient is a function of degree of saturation of soil and the following simple form can be used:

$$\chi = f(S_r) = S_r \tag{2}$$

Vertical and horizontal effective stresses can subsequently be defined as below, with K_o represents the coefficient of earth pressure at rest:

$$\sigma_v' = (\sigma_v - u_a) + S_r s \tag{3}$$

$$\sigma_h' = (\sigma_h - u_a) + S_r s = K_o (\sigma_v - u_a) + S_r s \tag{4}$$

As suction in the field changes, the effective stress of the liner will also change, which follows the following equation:

$$\Delta \sigma_v' = \Delta \sigma_h' = S_r \Delta s + s \Delta S_r \tag{5}$$

Assuming the K_o condition applies, which is reasonable for this case, the relationship below holds:

$$\Delta \epsilon_v \text{ or } \Delta \epsilon_{vol} = \frac{1}{E} \Delta \{ [(\sigma_v - u_a) + S_r s] - 2\nu [(\sigma_h - u_a) + S_r s] \} \tag{6}$$

where E is the modulus of elasticity with respect to change in net stress and ν is the Poisson ratio of the soil. The following figure shows changes in the vertical and horizontal effective stresses due to changes in the soil suction, which have been derived using Figure 3, Figure 4 and Equation (5).




Figure 5 Changes in vertical and horizontal effective stresses with time

The K_o condition only holds when soil blocks do not develop as a result of cracks that develop due to desiccation. In the case of crack, the horizontal net stress follows:

$$(\sigma_h - u_a) = \frac{\nu}{(1-\nu)}(\sigma_v - u_a) - \frac{(1-2\nu)}{(1-\nu)}S_{r,s} \quad (7)$$

The changes in vertical and horizontal strains in the event of crack can be expressed as:

$$\Delta\varepsilon_v = \frac{1}{E} \Delta\{[(\sigma_v - u_a) + S_{r,s}] - 2\nu S_{r,s}\} \quad (8)$$

$$\Delta\varepsilon_h = \frac{1}{E} \Delta\{(1-\nu)S_{r,s} - \nu[(\sigma_v - u_a) + S_{r,s}]\} \quad (9)$$

3.1 Two-Independent Stress-State Variable Approach

The formulation of this approach is outlined in Fredlund and Rahardjo (1993), where changes in two state variables used (i.e. net stress and suction) and the resulting effects are considered separately.

In the case of the K_o condition ($\Delta\varepsilon_v = \Delta\varepsilon_{vol}$), the volumetric strain is given as:

$$\frac{(1+\nu)(1-2\nu)}{E(1-\nu)} \Delta(\sigma_v - u_a) + \frac{(1+\nu)}{H(1-\nu)} \Delta s \quad (10)$$

In the above equation, H represents the modulus of elasticity of the soil with respect to suction change (the 2nd stress state variable), while as described before, E signifies the modulus of elasticity for the effect of net stress (the 1st stress state variable) change.

During crack, the horizontal net stress is defined as:

$$(\sigma_h - u_a) = \frac{\nu}{(1-\nu)}(\sigma_v - u_a) - \frac{E}{H(1-\nu)} s \quad (11)$$

The changes in vertical strain ($\Delta\varepsilon_v$) and horizontal strains ($\Delta\varepsilon_h$) after crack are formulated as:

$$\frac{1}{E} \Delta\{(\sigma_v - u_a) - 2\nu(\sigma_h - u_a)\} + \frac{1}{H} \Delta s \quad (12)$$

$$\frac{1}{E} \Delta\{(\sigma_h - u_a) - \nu[(\sigma_v - u_a) + (\sigma_h - u_a)]\} \quad (13)$$

4. PARAMETERS USED IN COMPUTATION

The following parameters have been used in the computation and the values have been derived as outlined in this section.

- 1) Coefficient of earth pressure at rest (K_o)
- 2) Poisson ratio (ν)
- 3) Modulus of elasticity with respect to change in net stress (E)
- 4) Modulus of elasticity with respect to change in suction (H)

4.1 Coefficient of Earth Pressure at Rest (K_o)

The K_o value was determined from the experiment carried out in Geodelft, Netherlands. The value is equal to 0.52.

4.2 Poisson Ratio (ν)

The Poisson ratio (ν) is calculated from the elastic theory as follows (with K_o equal to 0.52):

$$\nu = \frac{K_o}{1 + K_o} = 0.34 \quad (14)$$

4.3 Modulus of Elasticity with Respect to Change in Net Stress (E)

The E value has been derived using the elastic theory from the saturated oedometer test data for the unloading-reloading, which is deemed to be within the elastic range:

$$m_v = \frac{\Delta e}{(1+e_0) \Delta \sigma'} = \frac{1}{E} \frac{(1+\nu)(1-2\nu)}{(1-\nu)} \quad (15)$$

where m_v is the coefficient of volume compressibility of soil. The average m_v value obtained from the saturated oedometer test results of the PEBSM specimen compacted at dry side as shown in Figure 6 is $1.798 \times 10^{-5} / \text{kPa}$. Thus, the corresponding E value is 36,134 kPa.




Figure 6 Oedometer test result on a saturated compacted PEBSM specimen

4.4 Modulus of Elasticity with Respect to Change in Suction (H)

The H value was computed from the e-log suction plot that had been obtained while determining the SWCC curve (Schanz et al., 2004). The SWCC had been determined at three-dimensional free swell/shrink conditions. Therefore, the following relationships hold:

$$\Delta\varepsilon_v = \Delta\varepsilon_{vol} = C_i \Delta(\sigma_v - u_a) + C_a \Delta s \quad (16)$$

$$C_i = \frac{\Delta e}{(1+e_0) \Delta(\sigma_v - u_a)}; C_a = \frac{\Delta e}{(1+e_0) \Delta s} \quad (17)$$

Analogous to the unloading-reloading path, from which the E value has been derived, the corresponding drying-wetting cycles of the PEBSM should also be used to determine C_a value. However, due to the unavailability of the wetting data, only the drying path has been considered in the derivation of C_a value. The following figure shows the drying test on the material.




Figure 7 Change in void ratio with increasing suction from a drying test on compacted PEBSM

The void ratio-suction curve exhibits a bimodal characteristic with negligible changes for suction above 500 kPa. The linear portion of the curve up to 500 kPa suction is within the suction range, at which the material was subject to in the field and thus can be used to determine the C_a value. From the curve, the C_a value is 1.017×10^{-4} /kPa, and thus a H value of 29,500 kPa as for this case $C_a = 3/H$.

5. DEFORMATION AND SETTLEMENT

Computation of settlement and deformation as a result of the change in suction, which was measured by the tensiometer, has been carried out using the parameters derived as described in the preceding section.

5.1 Computation using Single-Valued Effective Stress Concept

As described in Section 2, a change in the net vertical stress ($\Delta(\sigma_v - u_a)$) of 20.6 kPa was applied on the compacted PEBSM layer after placement. The corresponding change in the net horizontal stress ($\Delta(\sigma_h - u_a)$) is therefore equal to 10.7 kPa. The initial suction of the PEBSM was determined from the SWCC given the placement water content and dry density of the compacted layer and the value was 4.4 MPa. Immediately after placement, the tensiometer measured 20.1 kPa and therefore the material was subjected to a significant suction change once placed in-situ. The corresponding change in degree of saturation of 59% can be computed from the SWCC.

The initial strain and deformation due to placement can be computed and the values are summarised in the following table.

Table 1 Initial Strain and Deformation Computed using the Single-valued Effective Stress Concept

	Without cracks	With cracks
Vert. strain, ϵ_v (%)	-3.3	-3.2
Hor. strain, ϵ_h (%)	0	-3.3
Vert. deform. , d_v (cm)	-2.3	-2.3
Hor. deform. , d_h (cm)	0	-3.3

Note: -ve indicates expansion

5.2 Computation using Two-Independent Stress-State Variable Approach

As mentioned earlier, the H value for the compacted PEBSM layer was derived from the drying path. Realistically, the value for the wetting path is much higher than that from the drying cycle. The following table summarises the initial strain and deformation due to placement computed using the two-independent stress state variable approach.

Table 2 Initial Strain and Deformation Computed Using the Two-independent Stress-state Variable Approach

	Without cracks	With cracks
Vert. strain, ϵ_v (%)	-3.3	-1.6
Hor. strain, ϵ_h (%)	0	-1.7
Vert. deform. , d_v (cm)	-2.3	-1.3
Hor. deform. , d_h (cm)	0	-1.7

Note: -ve indicates expansion

In this computation, the realistic H value used in the computation was first approximated by matching the settlement plot from both approaches. It is later demonstrated that taking the realistic H value of 8 to 10 that of the drying is reasonable and an average value of 9H (i.e. 265,500 kPa) was subsequently used.

The subsequent changes in vertical and horizontal strains were computed based on an assumption that the changes in vertical and horizontal net stresses are equal to zero. This is adopted for both approaches when computing the evolution of deformation and settlement due to changes in suction of the PEBSM layer on site.

5.3 Comparison of Computed Strain and Settlement

It is shown in the two tables that the use of two different approaches affects the initial strains and deformation computation for the case with cracks with the two-independent stress-state variable approach estimating half the values compared with the single-valued effective stress concept.

The following figure illustrates that, for the case of K_0 condition, the use of H value from the drying curve result in much higher settlement estimated using the two-independent stress-state variable approach. This is inconsistent since at the K_0 condition, cracks do not occur and both approaches should give approximately the same result.




Figure 8 Comparison of settlement with time from two different approaches

The variation of time-settlement plot for the two-independent stress state variable approach is shown in the following figure using the realistic H value equal to 8 and 10 times that determined from the drying test as described earlier. It is demonstrated that an average value of 9H provides the best fit to the settlement plot from the single-valued effective stress concept.




Figure 9 Determination of actual H value

The evolution of vertical strain assuming K_0 condition is shown in Figure 10 for both methods. The single-valued effective stress concept consistently gives lesser vertical strain compared with that given by the two-independent stress-state variable approach, although the magnitude does not differ significantly.

Figure 11 and Figure 12 demonstrate that the two-independent stress-state variable approach produce lower values of vertical and horizontal strains for the case when crack occurs.




Figure 10 Vertical strain with time computed using the two approaches (K_0 condition)




Figure 11 Vertical and horizontal strains computed using the single-valued effective stress concept (after crack occurs)




Figure 12 Vertical and horizontal strains computed using the two-independent stress-state variable approach (after crack occurs)

5. CRITICAL SUCTION AT FIRST CRACK OCCURRENCE

Resistance to cracks is provided by the tensile strength of the soil and thus crack occurs when the negative net horizontal stress exceeds this value. Nevertheless, when desiccation takes place, the extent of cracks in the PEBSM layer in the field may not be

sufficiently deep to facilitate full development of preferential flow paths.

The suction value, at which cracks first occur is defined as the critical suction (s_{cr}) and the value can be computed by equating the net horizontal stress with the maximum tensile strength (t_{max}). Schanz et al. (2004) reported that t_{max} value of the PEBSM is 20 kPa on average.

The following equations represent the critical suction for the single-valued effective stress concept and the two-independent stress-state variable approach, respectively.

$$s_{cr} = \left[\frac{\nu}{(1-\nu)} (\sigma_v - u_a) - t_{max} \right] \frac{(1-\nu)}{(1-2\nu)} \frac{1}{S_r} \quad (18)$$

$$s_{cr} = \left[\frac{\nu}{(1-\nu)} (\sigma_v - u_a) - t_{max} \right] \frac{H(1-\nu)}{E} \quad (19)$$

Equation (18) must be solved iteratively since S_r is the function of suction, while s_{cr} from Equation (19) can be computed straightforward since both E and H are assumed to be constant with net vertical stress and suction, respectively. Nevertheless, it is imperative to note this assumption may not be always valid since in reality, E , H and t_{max} are also stress and suction dependent.

The critical suction can also be plotted as a function of the total vertical stress using both the above equations. The following figure shows such plot for the PEBSM studied.





Figure 13 Critical suction versus total vertical stress computed using the two approaches

The above figure reveals that at the applied total vertical stress of 20.6 kPa (the air pressure is atmospheric), the s_{cr} value is 85 kPa computed using the single-valued effective stress concept and 147 kPa using the two-independent stress-state variable approach. At any given applied total vertical stress, the two-independent stress-state variable approach gives a higher value of s_{cr} compared with the other approach. Further detailed investigation will warrant clarity at which cracks really commence during drying.

Considering that the maximum measured suction is only approximately 50 kPa (see Figure 3), cracks will not occur in the compacted PEBSM layer. It may not be the case when polymer is not added to the compacted bentonite-sand mixture due to presence of macro- and micro-pores within the mixture.

The mechanism of crack in the compacted bentonite-sand mixture has been described in detail by Agus (2005). Consider a representation of a compacted bentonite-sand mixture in Figure 14. A rapid desiccation results in movement of water in the inter-aggregate pores (macro-pores), which is not accompanied by sufficient macro-pore volumetric contraction. The presence of polymer in the compacted mixture will prevent this rapid desiccation process to occur, at least at low suction (i.e. below 100

kPa), which is practically even higher than the maximum value that can occur in the field when the compacted PEBSM layer is used in landfill.



COMPACTED BENTONITE-SAND MIXTURE

Figure 14 Possible representation of a compacted bentonite-sand mixture (from Agus, 2005)

6. POSSIBLE APPLICATIONS

Due to its characteristics as described, the compacted PEBSM is suitable for landfill application. The material is better placed under a drainage layer to ensure that suction remains low and deep cracks are not present during the landfill design life. The effectiveness of placing the compacted PEBSM below the waste is questionable since interaction between the bentonite-polymer with leachate from the landfill may degrade the beneficial properties of the mixture.

7. CONCLUSION

An investigation into the behaviour of a compacted PEBSM has been conducted by means of a field case study. The following conclusions can be drawn from the outcome of the study.

- 1) A maximum suction value of 50 kPa was measured during an approximately 4-year period in the case study presented in this paper. The corresponding drop in degree of saturation as computed from the soil-water characteristic curve (SWCC) is hardly below 80%, which indicate a good water retention capability of the material.

- 2) Strain and deformation computed using the two-independent stress-state variable approach are approximately half those derived using the single-valued effective stress concept. The former computation is realistic when adopting a realistic modulus of elasticity with respect to change in suction (realistic H) of 8 to 10 times H derived from the drying test.
- 3) Critical suction at which cracks start to occur (s_{cr}) has been computed and the value is consistently lower for the two-independent stress-state variable approach at any given net or total vertical stress (with atmospheric air pressure).

8. REFERENCES

- Agus, S.S. (2005) An Experimental Study on Hydro-Mechanical Characteristics of Compacted Bentonite-Sand Mixtures. Doktor-Ingenieur Dissertation, Bauhaus-University Weimar, Germany.
- Agus, S.S., Arifin, Y.A., and Schanz, T. (2007) "Settlement and swells/shrink behaviour of a compacted polymer-enhanced bentonite-sand mixture as induced by field mechanical loading and wetting-drying cycles", Proceeding of Brazilian Symposium of Unsaturated Soils, Salvador, Brazil, 2007.
- Arifin Y.F., Agus S.S., and Schanz T. (2016) "Swelling pressure and hydraulic conductivity of compacted polymer-enhanced bentonite-sand mixture", Proceeding of Geotechnische Aspekte in Umweltschutz 2006, Stahlman and Rosenberg Edition. Braunschweig, 87-98.
- Fredlund D.G., and Rahardjo H. (1993) Soil Mechanics for Unsaturated Soils. John Wiley & Sons. Canada.
- Schanz, T., Agus, S.S., and Tscheschlok, G. (2004) "Hydraulisch-mechanische Eigenschaften einer polymerverbesserten Sand-Bentonit- Mischung beim Einsatz im Deponiebau", Geotechnik, 27, 4: pp344-355.

ACKNOWLEDGEMENT

The authors would like to express sincere gratitude to the late Prof. Dr.-Ing. habil. Tom Schanz for his guidance when this research work was carried out in Bauhaus-University Weimar, Germany. He was also the authors' PhD supervisor in the same university. He passed away in 2017 in Bochum, Germany, where he and his family lived.